


NOTES:

1. IF PIPE ON BOTH SIDES OF VALVE IS NOT DIP, THEN VALVE MUST BE SUPPORTED AND STRPPED DOWN TO A CONCRETE PAD (SEE DRAWING W-25).
2. STUB OUT MUST BE HYDROSTATICALLY TESTED WITH REST OF WATER MAIN.
3. IN LIEU OF SLIP-JOINT AND COMPRESSION PLUG, AN M.J. JOINT MAY BE USED WITH A M.J. PLUG

CONCRETE COLLAR THRUST RESTRAINT SEE DRAWING W-30 FOR EXACT DIMENSIONS FOR VARIOUS PIPE DIAMETERS

REVISIONS


City of Cumming
 Department of Utilities - Distribution and Collection Division

STUB OUT DETAIL



W-16