


NOTES:

1. IF PIPE ON BOTH SIDES OF VALVE IS NOT DIP, THEN VALVE MUST BE SUPPORTED AND STRAPPED DOWN TO A CONCRETE PAD.
2. STUB OUT MUST BE HYDROSTATICALLY TESTED WITH REST OF WATER MAIN.
3. IN LIEU OF SLIP-JOINT AND COMPRESSION PLUG, AN M.J. JOINT MAY BE USED WITH A M.J. PLUG
4. STUB OUT PLUG SHALL BE TAPPED W/ 3/4" COPPER CORPORATION STOP & ROUTED TO METER BOX & CURB STOP

CONCRETE COLLAR THRUST RESTRAINT SEE DETAIL W-16 FOR EXACT DIMENSIONS FOR VARIOUS PIPE DIAMETERS



CUMMING UTILITIES

LATEST REVISION

07/14/2017

CITY OF CUMMING

DEPARTMENT OF UTILITIES

STUB OUT DETAIL

DETAIL NUMBER:

W-9

SCALE: NOT TO SCALE